


DRAFT TENDER SCHEDULE

Issued to :


Original / Duplicate

Construction of dry waste collection and sorting centre at Sahakarangara in ward no. 08, Kodigehalli sub division.

Sl. No.	Approved Quantity	Description	Unit	Rates	
				In Figures	In Words
1	45	KSRB 2-1.1: Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications	cum	144.16	
2	25.34	KSRB 2-2.2 : Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in Hard soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications	cum	259.7	
3	7.53	KSRB 4-1.7 : Providing and laying in position plain cement concrete of mix M10 with OPC cement @ 220 Kgs with 20mm and down size graded granite metal coarse aggregates @ 0.84 cum and fine aggregates @ 0.56 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications,	cum	5189.76	
4	7.97	KSRB 5.2-2 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammered dressed in courses not less than 20 cms high, bond stones, at two m. apart in each course including cost of materials, labour, curing complete as per specifications	cum	3765.12	
5	5.97	KSRB 5.3-3 : Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stone chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specification	cum	4458.36	


**Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.,
Bangalore - 560 092**

Sl. No.	Approved Quantity	Description	Unit	Rates	
				In Figures	In Words
6	5.61	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 kgs, with 20mm and down size graded granite metal, coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplasticiser @ 3lts conforming to IS 9103-1999 reaffirmed-2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, walls (any thickness) including attached plasters, column, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour, HOM of machinery, curing, complete as per specifications	cum	5952.96	
7	0.504	KSRB 4.9.2: Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications	qtl	76900.88	
8	6.64	KSRB 2-4 : Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50mm, and lift upto 1.5m, including cost of all labour complete as per specification	cum	69.96	
9	16.25	KSRB 2.5 : Earthwork excavation (in deposited soil) and filling sides of foundation upto plinth in layers not exceeding 20cms, in depth, compacting each deposited layer by ramming after watering with lead upto 50mm, and lift upto 1.5m, including cost of all labour complete as per specifications	cum	232.14	
10	1.53	Providing and fabricating structural steel truss work including 2 coats of enamel paint over a coat of shop paint to design, drawing furnished by the consultant	MT	90000	
11	90.25	Providing metacolor sheet roofing including acoustic treatment etc complete as per detail drawing furnished by the consultant	Sqm	1200	
12	26.9	KSRB 5-14 : Providing and constructing precast concrete solid blocks with compressive strength not less than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications	Sqm	975.2	
13	6.5	KSRB: 7.5 Providing and fixing pull and push type rolling shutters of approved make out of 18 gauge, 75mm wide cold rolled steel laths of convex corrugation, with side guides and bottom rail, with interlocking arrangements for steel laths by means of alternate clips, suspension shaft with High tension coil type springs two numbers, mounted on specially designed pipe shaft, with bracket plates, guide channels, ball bearing arrangements, for inside & outside locking with push & operations complete including pulling hooks, 4nos handles with hall fittings and accessories, painted with a coat of red lead paint (without top cover) cost of materials, labour, HOM of machinery complete as per specifications. Shutter size 3mx2.8m	Sqm	2820.66	


Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092


Sl. No.	Approved Quantity	Description	Unit	Rates	
				In Figures	In Words
14	3	KARB 7.6 Providing and fixing top covers made out of 20 guage M.S. sheet over m pull and push rolling shutters bent to shape including cost of red lead primer coat of painting, materials, labour, HOM of machinery complete as per specifications. Shutter size 3mx2.8m	m	645.54	
15	168	KSRB 7.9 : Providing and fixing M.S. grill work for windows and ventilators weighing 21 kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifications.	kg	98.58	
16	28.1	KSRB 15.3.9: Providing 18mm thick cement plaster in single coat with cement mortar 1:6, to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specification	Sqm	185.5	
17	28.1	KSRB 15-16.1: providing and finishing external walls in two coats with water proof cement paint of approve brand and shade to give an even shade after thorough brooming the surface to remove all dirt and losse powdered material, free from mortar dops and other foreign matter cost of materials, labours, complete as per specifications	Sqm	79.5	
18	3.25	KSRB- 4-1.5 : Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.64 cum and fine agggregares @ 0.43 cum with superplastisiser @ 3lts confirming to IS9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications	cum	5744.14	
19	32.49	Vaccum De-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator HOM of machinery Screed Vibratiry, Power Floater, blade and disc etc., with all lead and lift	Sqm	97.2	

ಕರಡು ಬೆಂದರ್ ವದ್ಯೂಲ್‌ನ್ನು

ತಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ 11/2

ತಿದ್ದುಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ


ಅನುಮೋದನೆ ನೀಡಲಾಗಿದೆ.



SuperIntending Engineer

Yelabank Zone

BBMP, Bangalore - 92



Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92